

Town of Lysander 2023 Pavement Management Work Plan

Updated 3/22/23

Total Budget = \$656,000 (Road Maintenance Fund) + \$466,000 (Construction & Improvement Fund) = \$1,122,000

Name	From	To	Length (ft)	Width (ft)	Area (sq)	Repair Type	Estimated Cost
Esprit Glade	Town Center	Deep Glade	1854	24	4944	Mill & Fill 1.5"	
Mourning Dove	Esprit Glade	Van Wei Drive W	2585	24	6893	Mill & Fill 1.5"	
Stanford Drive	Drakes Landing	River Road	1900	24	5067	Mill & Fill 1.5"	
Jayhawk Circle	Stanford Drive	Stanford Drive	1792	24	4779	Mill & Fill 1.5"	
Royal Scarlet Drive	Town Center Rd	Deep Glade	1568	24	4181	Mill & Fill 1.5"	
Melvin Drive S	West of Lightfoot	Cul-de-sac	1190	24	3173	Mill & Fill 1.5"	
Lightfoot lane	Melvin Drive S.	Cul-de-sac	745	24	1987	Mill & Fill 1.5"	
Misty Cove Circle	Melvin Drive N.	Cul-de-sac	1227	24	3272	Mill & Fill 1.5"	
Porter Cottage	Melvin Drive N.	Turn around	536	24	1429	Mill & Fill 1.5"	
Green Leaf Drive S.	End of new top	Dead End	930	24	2480	Mill & Fill 1.5"	
Glen Abby Terrace	Frenchmans Creek	Frenchmans Creek	1470	24	3920	Mill & Fill 1.5"	
Camerra Way	Rte. 370	Cul-de-sac	636	24	1696	Mill & Fill 1.5"	
Brundage Road ¹	East AB Entrance	West Entry	1850	36	7400	Mill & Fill 2"	
Drakes Landing ²	LP N. of Oak Brook	Stanford Drive	4123	36	16492	Mill & Fill 2"	
Melvin Drive N.	River Rd	Cul-de-sac	1126	28	3503	Mill & Fill 1.5"	
Melvin Drive S.	River Rd	Concrete VG	668	32	2375	Mill & Fill 1.5"	
Exeter Drive	Curve @ North End	Mott Road	1175	26	3394	Top Course 1.5"	
Eden Lane	Exeter Drive	Mott Road	712	26	2057	Top Course 1.5"	
Willow Bend Drive	Rte. 370	Dead End	398	24	1061	Chip Seal	
Glenbrook Drive	Rte. 370	Cul-de-sac	1510	24	4027	Chip Seal	
Jayhawk Circle Outfall	-	-	180	-	-	Pipe Replacement	
Gates Road Culvert	-	-	40	24	107	Stabilize Roadway	
Copperknoll Culvert	-	-	40	24	107	Stabilize Roadway	
Rabbit Lane Culvert	-	-	40	24	107	Stabilize Roadway	
Swamp Road Shoulder	-	-	40	8	36	Fill and stabilize	
Exeter/Eden Top Soil	-	-	-	-	-	Shredder/Screen	
CB/Gutter Repairs	-	-	-	-	-	Spot Repairs	
West Entry MH Repair	-	-	-	-	-	Saw Cut, Reset, Pave	
Willetts Pkwy CB	-	-	-	-	-	Replace 4 CB	
Crack Seal ³	-	-	-	-	-	Crack Seal	
TOTAL =							\$1,121,938

1. From end of newer asphalt top course paving east of AB Entrance to West Entry Road
2. From low point between Oak Brook and Partridgeberry to Van Wei West Intersection
3. Melia Park, Timber Banks, Clinton Heights, Holly Hill, Abbotts Landing, Springwoods, Brick Walk, Talamore & Radisson Neighborhoods